CAPSULE SUMMARY CT-1126

Cleary/Gibson Barn B is located at the corner of Lower Marlboro and Stephen Reid Roads in Huntingtown Maryland. This barn was originally part of the Gibson farm. It is situated on top of a hill that slopes down to the south and east below the barn. The barn is built on top of the hill. A farm road runs to the west gable end entrance. Another barn is situated immediately to the south of barn B. It is similar in appearance to Cleary/Gibson barn B. Barn B measures fifty-eight by twenty-six feet and is built of circular sawn lumber and wire nails. It has two sets of double doors on the east and west gable ends. The aisle plan and construction materials and techniques are typical of a barn of the mid-late twentieth century.

Maryland Historical Trust State Historic Sites Inventory Form

Magi No.

DOE __yes __no

1. Nam	e (indicat	e preferi	ed name)				
historic							
and/or common	Cleary/Gibso	n Barn	В				
2. Loca	ation						
street & number	Lower Marlt	oro Rd.	and Stephen	Reid Rds.		not for publi	cation
city, town	Huntingtown ⁻	d.	vicinity of	congressional d	istrict		
state MD			county	Calvert			
3. Clas	sification	n					
Category — district × building(s) — structure — site — object	Ownership public private both Public Acquisiti in process being conside not_applics	on Ac	atus _ occupied _ unoccupied _ work in progress cessible _ yes: restricted _ yes: unrestricted _ no	Present Use agriculture commerci education entertainn governme industrial military	al al nent nt	museum park private r religious scientific transpor	esidence c tation
·		perty	(give names a	nd mailing add	lresses	of <u>all</u> own	ners)
name Frank	Cleary						
street & number				teleph	one no.	: 257-949	90
Oity, town	ver Marlboro			and zip code		MD 2	20639
<u>5. Loca</u>	ation of L	egal	Descripti	on			
courthouse, registry of deeds, etc. Ca		Calvert	County Courtho	use liber		·-	
street & number Ma		Main St	eet (MD 765)	folio			
city, town Prince Frederick		state MD					
6. Rep	resentati	on in	Existing	Historical	Surve	ys	
title				·			
date				federal _	state	county	loca
pository for su	urvey records		4				
city, town					state		

7. Desc	ription			Survey No.CT-112 6
Condition excellent × good fair	deteriorated ruins unexposed	Check one X unaltered altered	Check one X original site moved date of move	

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today. See Attachment.

8. S	ignificance	Survey No.	CT-112 6
1600-	-1499 archeology-historic conservation -1599 agriculture economics -1699 architecture education -1799 art engineering -1899 commerce exploration/settlem	ng landscape architecture law literature military music	e religion science sculpture social/ humanitarian theater transportation other (specify)
Specific	dates Builder/Architect		
check:	Applicable Criteria: A B C D and/or Applicable Exception: A B C D Level of Significance:nationalstate		
support	both a summary paragraph of significance an	d a general statement of	of history and

10. Geographic	cal Data		
Acreage of nominated property Quadrangle name North Beach UTM References do NOT comp		rences	Quadrangle scale 1:24000
Zone Easting Nor	thing	BZone	Easting Northing
C		D F H	
Verbal boundary description a	nd justification		
List all states and counties fo state	code	county	unty boundaries code
state	code	county	code
11. Form Prepa	ared By		
name/title Tora L. Wil c/o Calvert County Hi organization Dept. of Pla	liamsen-Ber storic Dist anning and Z	rict Commissi	June 30 1990
street & number Courthouse		tel	535-1600 ephone
city or town Prince Frederi	ck	sta	MD ate

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

7. DESCRIPTION CT-1126

Cleary/Gibson Barn B is located at the corner of Lower Marlboro and Stephen Reid Roads in Huntingtown Maryland. This barn was originally part of the Gibson farm. It is situated on top of a hill that slopes down to the south and east below the barn. The barn is built top of the hill. A farm road runs to the west gable end entrance. Another barn is situated immediately to the south of barn B. It is similar in appearance to Cleary/Gibson barn B. Barn B measures fifty-eight by twenty-six feet and is built of circular sawn lumber and wire nails. It has two sets of double doors on the east and west gable ends.

The barn is divided into six eight foot bays. Two sets of twelve foot wide double doors are centered on the gable ends, thereby creating an aisle plan barn. Continuous cinder block foundations support the barn on the north and south sides. The frame is circular sawn and toe-nailed with wire nails. Plain vertical wall siding with eleven hinged ventilation doors on both the north and south sides covers the exterior. The roof is covered with standing seam metal. The rafters are on four foot centers and rest on a flat false plate. There are windbraces on all four diagonals. In addition to the windbraces, three collars and king posts help support the roof. Tier poles are circular sawn and separated by forty-one inches vertical distance. Poles down the center are two timbers joined by blocks that have been inserted between. The tier poles are then laid on top of these blocks. The central posts rest on a continuous sill which is raised on cinder blocks.

8. SIGNIFICANCE CT-1126


This barn is architecturally significant for several reasons. It is a typical representative of the standard mid-late twentieth century tobacco barn. All of the materials and techniques are consistent with this date. In addition, the strictly linear aisle plan is typical, as is the extensive control of ventilation, by means of closed-off sills and hinged ventilation doors. The barn is also interesting because of its location immediately adjacent (with less than fifteen feet between) to another tobacco barn.


This barn also yields information regarding agricultural history in Southern Maryland. In February 1990, a tobacco barn survey was initiated in order to study the tobacco barns of Calvert County. Until fairly recently, tobacco was the most important farm crop of the county. More acreage was devoted to its cultivation than for both of the next most extensive farm products (corn and wheat). The barns and stripping houses related to this "Tobacco Culture" are widely recognized as the most common element on the rural landscape. These structures are also the most threatened, as the market for tobacco declines. They seem to have, at present, only limited capabilities for re-use. Many barns and stripping houses now stand empty. The purpose of this survey has been to gather information and document a wide sample of these structures before they disappear from the landscape.

Historical Period theme(s): ca. 1950-; Tobacco; Agriculture Geographical Organization: Western Shore Chesapeake Bay Calvert Cty MD Chronological/Developmental Period: ca. 1950-Present Resource Type(s): Tobacco Barn

It is unknown exactly what date this barn was built. The materials and techniques used are consistent with the twentieth century, and the lack of mortise and tenon joints or other time-consuming carpentry probably date it to the latter half of this century. Ms. Paula Mask recalls aiding in the harvest of vegetables on the farm approximately ten years ago. She states that, at that time, tobacco was still grown on the farm. The farm has passed from the original owners, the Gibsons, to the Cleary family, and tobacco is no longer grown. The barn appears to be used solely for storage.

#2099 - 5/14/90 - Mr. Cleary, Huntingtown Rd. Huntingtown MD 20639. Rt. 4 south to 262 at Sunderland, 9/10 mile to barns on left at corner of Stephen Ried Road. Private ownership, occupied. PM and Unaltered, original site, good TW recorders. Sunny weather. condition. Continuous cinder block foundations on north and south sides. Frame circular sawn and toe-nailed with wire nails. Plain vertical wall siding with eleven hinged ventilation doors on both north and south sides. Standing seam metal roof. Rafters are on four foot centers and rest on a flat false plate. Windbraces on all four diagonals, three collars. Posts are toe-nailed to plate. Tier poles are circular sawn and separated by forty-one inches vertical distance. Poles down the center are two timbers joined They rest on a continuous sill which is raised on cinder blocks. King posts help support the roof also.







CLEARY BIBBON & TORA L WILLIAMSEN MAY , 1990